

TOWN OF CHAPLIN

Senior Center & Library Parking Lot Improvements, Chaplin Street Intersection Realignment at Route 198, and New Sidewalk Construction

ADDENDUM NO. 1

(March 16, 2026)

TO ALL PROSPECTIVE BIDDERS:

This Addendum includes clarifications to the Contract Documents, along with responses to questions received, as noted below.

Please acknowledge receipt of the Addendum a part of your bid. This Addendum, consisting of 1 page, is issued by the Town of Chaplin, Connecticut.

QUESTIONS RECEIVED AND ANSWERS

Q.1. Can any recycled asphalt product (RAP) be incorporated in Class 1 and Class 2 Bituminous Concrete mix that will be used in the project?

A.1. RAP shall not be incorporated in any of the Class 1 and Class 2 Bituminous Concrete mix used in this project. Furthermore, all delivery slips shall be submitted to the Town of Chaplin at the end of each work day. This applies to all material deliveries and material certification documentation for all manufactured items incorporated in this project.

DOCUMENTS MODIFIED

On plan sheets 3 & 6 a new Portland Cement Concrete Driveway Ramp opposite Route 198 Station 13+75± (LT) has been added. Also added to sheet 6 is the Sight Distance for this driveway in both directions on Route 198. An angle has also been added where the new Chaplin Street Baseline meets the Route 198 Baseline.

The Form For General Bid Section 00300 has been updated to include a line item for the Portland Cement Concrete Driveway Ramp.