

TOWN OF CHAPLIN

Senior Center & Library Parking Lot Improvements, Chaplin Street Intersection Realignment at Route 198, and New Sidewalk Construction

ADDENDUM NO. 2

(March 18, 2026)

TO ALL PROSPECTIVE BIDDERS:

This Addendum includes clarifications to the Contract Documents, along with responses to questions received, as noted below.

Please acknowledge receipt of this Addendum as part of your bid. This Addendum, consists of 1 page, issued by the Town of Chaplin, Connecticut.

QUESTIONS RECEIVED AND ANSWERS

- Q.1. Item 5 "Processed Aggregate Base 6" Thick" in the Form for General Bid does not agree with bullet "C" in the "Typical Reconstructed Chaplin Street Cross Section" detail on Plan Sheet 9. Which one is correct and what is the correct quantity?
- A.1. Bullet "C" in the cross section detail should have read 6" Processed Aggregate Base. Accordingly, the quantity in Item 5 in the Form for General Bid is correct and the depth of aggregate base is to be 6".
- Q.2. There are no electrical service plans in the plan set for wired lighting. Are there plans for this?
- A.2. It shall be the responsibility of the contractor to develop a plan for the lighting system layout (conduit runs with hand holes) and connection to a power source in the Senior Center/Town Library building (in basement at northwest corner of building - side facing cemetery), or, instead, by the contractor retaining a qualified subcontractor for this type of work. The plan shall be reviewed and approved by the town Building Official.

Compensation for this work shall be included in the unit price of bid items related to wired lighting devices and any light pedestals to be removed from an existing wired system. No additional compensation shall be made for plan preparation; any additional items that may be included in the plan; and components/connection to an existing power source.