

# TOWN OF CHAPLIN

## Senior Center & Library Parking Lot Improvements, Chaplin Street Intersection Realignment at Route 198, and New Sidewalk Construction

### **ADDENDUM NO. 3**

(March 26, 2026)

#### **TO ALL PROSPECTIVE BIDDERS:**

This Addendum includes clarifications to the Contract Documents, along with responses to questions received, as noted below.

Please acknowledge receipt of this Addendum as part of your bid. This Addendum, consists of 7 pages, issued by the Town of Chaplin, Connecticut.

#### **QUESTIONS RECEIVED AND ANSWERS**

Q.1. Are the measurements for items 13 and 14, supposed to be in SF instead of SY?

A.1. No. The Unit of Measure of "SY" for each item is correct in the Form for General Bid REV 2.

Q.2. Should there be Processed Gravel in the Bituminous Concrete Parking Lot Detail on plan sheet 9?

A.2. No. The only place 700 CY (not tons) of Processed Aggregate Base 6" Deep (Bid Item 5, REV 2) is used is within the reconstructed portion of Chaplin Street (see Chaplin Street cross section on plan sheet 9).

Q.3. Is any Class PCC044622 High Performance Concrete required anywhere on this project?

A.3. No. CT DOT Class PCC0446Z, 4,400 psi concrete, is to be used on this project. 4,400 psi concrete is noted on plan Sheet 9 for use in all sidewalk construction and shall be construed as DOT Class PCC0446Z.

#### **DOCUMENTS MODIFIED AND ADDED**

Connecticut Department of Transportation's "Highway Standard Drawing HW 811\_01, Concrete Curbing," is attached to this addendum and shall be incorporated into the project plan set as a detail for Precast Concrete Curbing installation (1 page).

The Form for General Bid Section 00300 has been updated to include a line item (#8) for Portland Cement Concrete Curbing and is attached to this addendum (4 pages).